


MANTEL INSTALLATION GUIDE



- 1. LOCATE DESIRDED MANTEL HEIGHT
- 2. LOCATE SOLID BACKING
- 3. DRILL HOLES IN WOOD LEGDER
- 4. SECURE LEDGER WITH LAG BOLTS (LEVEL)
- 5. APPLY A GENEROUS AMOUNT OF PL CONSTRUCTION ADHEISIVE AT TOP OF LEDGER.
- 6. SET MANTEL IN PLACE WITH SUPPORTS, LET DRY FOR 24 HOURS.
- 7. ALWAYS SEAL WITH PENITRATING SEALER

1201 E. WAKEHAM AVENUE SANTA ANA, CA 92705-4504 714-836-5757 866-99-STONE FAX 714-836-4433 WWW.PACIFICSTONE.NET