

Technical Data Sheet

Pacific Stone Design, Inc.



Product Description:

PSD's architectural pre-cast concrete units comply with manufacturing and testing procedures, quality control recommendations, and follow dimensional tolerances of 1/4", unless otherwise indicated. The architectural pre-cast concrete includes wall caps, corbels, columns, coping, balustrade, quoins, pavers, finials, moldings or any other decorative element designed to be cast out of concrete.

Quality Insurance:

PSD has over 10 year of pre-cast manufacturing experience. PSD pre-cast is inspected and tested in accordance with ACI 533.

Delivery/Storage:

PSD pre-cast will be packaged to protect the finish during transport. Pre-cast should not be left packaged in direct sunlight for both coloration and curing reasons.

Limitations: Color variation is to be expected for all pre-cast products. Cement may cause irritation. Avoid contact. In case of contact with eyes, flush out with water immediately. If problem persists see a physician immediately.

Test Data: A trial mix was made and had a strength of 4590 psi @ 7 days and 5665 (average) psi @ 28 days.

Compression Test On Concrete

Sampled From : Batch # 1 @ Santa Ana Plant

Measure Slump: 5 in.

Mix: Type III Concrete

Spec. Str. (Psi): 4000 @ 28 days

2nd Spec. Str. (Psi): 0

Cast: 3/15/2006

Test Date 3/22/2006 4/12/2006 4/12/2006

Specimen #: 1-1 # 2-2

Cust. Spec #: 1 2 # 3-3

Age (Days): 7 Day 28 days 28 day

Dims (in): 6.01 x 12.00 6.01 x 12.00 6.01 x 12.00

Area (sq. in): 28.37 28.37 28.37

L/D or hp/tp: 2.00 2 2

Total load (ibf): 130218 156886 164546

Comp Str (psi): 4590 5530 5800

Corr Factor: 1.00 1 1

Corr Str (psi): 4950 5530 5800

Average 28 Day Strength: 5665

Procedure: ASTM C31, ASTM C39, ASTM C143


Specimen Shape: Cylinder

Specimen By: Jeff Carter

Delivered By: TLSC

Received on: 3/16/06

Compliance: Material Tested: Met



Installation:

- All installation of PSD pre-cast must comply with the preset masonry standards listed in ACI-533.
- PSD pre-cast must be installed to conform with structure tolerances within $\pm 1/4"$.
- Do not install units until supporting structure has been completed or attained minimum allowable design compressive strength.
- Install level, plumb, and true to line. Do not allow cumulative dimensional errors to develop.

Material:

1. Hi- Early Type III Cement: ASTM C 150
2. 1/4" Aggregates: ASTM C 33
3. Water: as required to produce a 4 inch slump
4. Silica Sand
5. Glass Fiber AR (Alkali Resistant)
6. Coloring Agent: ASTM C 979

Warranty:

A one-year limited warranty applies to all PSD products. Defective products will be repaired or replaced, during the warranty period, at no cost to the customer. Damages incurred from improper installation, vandalism, and acts of God are not covered.

Pacific Stone Design, Inc.
1201 E. Wakeham Santa Ana, CA 92705
Phone: (714) 836-5757 Fax: (714) 836-4433
Email: sales@pacificstone.net